

Greenfields Respite, Barnstaple (Devon CC / Pearce Construction) - Proposal and Pricing Review

TENDER DEADLINE: 12 NOON, 17 JULY 2026 Window & door replacement package at an **operational care home** (Derby Rd, EX32 7EZ). JCT MW 2024, start 31/08/2026, 12-week contract, 5% retention. No supplier quotes yet - every frame rate below is a **median from Fenster's supplier-rate register** (15,551 mined quote lines) with documented uplifts for this spec (PAS 24:2022, toughened-out/laminated-in safety glass, restrictors, white frames). Take-off: **77 openings** from drawing SWN-XX-XX-D-B-005 P2 (58 uPVC windows, 4 aluminium screens incl. 5 NSHEV smoke vents, 15 doorsets). Full item-by-item schedule in the accompanying Take-Off & Specification workbook.

Supply (benchmark + allowances)	Install labour (Fenster codes)	Tender sell ex VAT	VAT @20%	Total inc VAT
GBP 85,361.30	GBP 15,620.00	GBP 100,981.30	GBP 20,196.26	GBP 121,177.56

Package summary

Package	Qty	Supply	Labour	Sell ex VAT	Notes
uPVC windows & window screens, white (23 obscure-glazed bathroom units incl. 17nr ~2375x1140; escape windows with Jackloc restrictors + override to first floor; trickle vents; PAS 24)	58	GBP 36,030.12	GBP 9,520.00	GBP 45,550.12	BSW uPVC glazed medians by size band + GBP25/m² safety-glass uplift + GBP70/window hardware
Aluminium screens, white PPC - 2 full-height stair screens with 5nr NSHEV smoke vents linked to fire alarm + 2 entrance flank screens (WG-31/32)	4	GBP 16,917.37	GBP 1,600.00	GBP 18,517.37	BSW alu glazed medians + GBP950/vent AOV allowance (controls/connection by others)
Aluminium doorsets - 5 white (incl. main entrance with 'Greenfield's' fascia + letterbox, 2 double fire exits) + 5 brown RAL 8004 plant doors (incl. louvre double DG-03 and 3-leaf slide-fold DG-08)	10	GBP 18,970.91	GBP 3,250.00	GBP 22,220.91	BSW alu door medians (+10% RAL 8004) + ironmongery/signage allowances per spec 3.13
uPVC doorsets, white (3 fire exits with push pads + 2 access doors with latch/thumb turn)	5	GBP 3,718.36	GBP 1,250.00	GBP 4,968.36	BSW uPVC door median + ironmongery allowance
Perimeter sealing/pointing 542 lm @ GBP5/lm (PU foam + sealant both sides per 3.10.39)	1	GBP 2,711.70	-	GBP 2,711.70	Fenster standard rate
Tower access for window works (main roofing scaffold by others)	1	GBP 1,500.00	-	GBP 1,500.00	Spec 3.3.6
FENSA notification, certification + 10-year insurance-backed guarantee registration	1	GBP 600.00	-	GBP 600.00	Spec 3.10.43-44
Manifestation to glazed doors/screens (Approved Docs M1/M2 + N2)	1	GBP 350.00	-	GBP 350.00	Spec 2.7
Occupied-care-home sequencing, protection & Schedule of Condition (5%)	1	GBP 4,562.84	-	GBP 4,562.84	Spec 2.5 / 3.1

Key specification captured (full detail in Take-Off & Specification workbook)

- **Security:** windows PAS 24:2022, two-stage locking handles, toughened outer + laminated inner glass; ground-floor restrictors and first-floor ESCAPE windows with override restrictors (Jackloc Titan allowed); commercial-grade hardware, 300-series stainless fixings.
- **Glass:** safety glazing throughout (BS6262/EN 12600, kitemarked every pane), obscure to 23 bathroom/WC windows, clear elsewhere, Part K4 critical locations, max U 1.4 W/m²K, trickle vents to Part F.
- **Colours/materials:** uPVC and PPC aluminium, white inside and out - except plant/boiler doors in Brown RAL 8004; BS7412/BS7413 system approvals (evidence submitted with tender); frames marked to BS at 1m centres.
- **Fire:** push pads (single) / push bars (double) to fire exits, BS5499 signage both faces, DG-01/DG-09 external pull handles, NSHEV smoke vents to both stair screens, Part B1 escape compliance.
- **EPDM:** EPDM glazing gaskets with knock-in beads; PU foam/impregnated tape + sealant perimeter seals inside and out.
- **Programme:** quote by 17/07 noon; start 31/08/2026; 12 weeks; room-by-room sequencing agreed with site staff; FENSA install; prefab drawings for CA approval before manufacture; 10-yr IBG on DGUs.

Exclusions & RFIs (full list in workbook)

- Excluded: maglock/key-card/fire-alarm connections (client provisional sums 3.22.1/3.22.2 - interface prep only), NSHEV control wiring, scaffolding (towers only allowed), asbestos, blinds/curtains (PS 3.22.4), internal redecoration beyond making good.
- **RFI - scope gap:** 005 shows no elevations for WG-15 to WG-29, WF-10/11 or DG-13, but the floor plans reference WG-27 and DG-13 - confirm whether additional openings are in scope (NOT in this price).
- RFI: WF-22 duplicated on 005; second stair screen ref illegible; DG-08 slide-fold operation; DG-09 fascia sign supply; obscure pattern; AOV controls responsibility.
- Dimensions are drawing-guidance only ("final measurements by manufacturer") - technical survey before fabrication; window bay posts checked/replaced where necessary as noted on 005.